



OFFICE OF THE PRINCIPAL/ SECRETARY

Ph.-03252-240310

E-mail:mgclalpur@yahoo.co.in

www.mahatmagandhicollegelalpur.ac.in

MAHATMA GANDHI COLLEGE

(NAAC Accredited Grade- "B+" w.e.f. 16.09.2016)

LALPUR • P.O.-DALDALI • DIST- PURULIA • PIN-723130 (W.B.)

Ref. No.-.....

Date-.....

Notice

No. MGC/Quot./23/09/NIQ-11

Dtd. 23/09/2025

Quotations are invited from eligible contractor for performing the following works within 13/10/25 (Monday). of Rs. 68,808/-

Work tender Renovation of Administrative Building (Block-A) at M.G. College, Lalpur

SL. NO	Subject	SPECIFICATION
1	Renovation of Administrative Building (Block-A)	Description of the work: See attached file

Terms & Conditions:

1. GST and any other applicable taxes must be mentioned separately.
2. Quotation must be submitted on letterhead with seal and signature.
3. Work must be completed within 7 days of issuing the work order.
4. Vendors must submit valid trade license, PAN, and GST registration documents.
5. The last date of submission of the quotation is 13/10/25 (Monday) by 3:00 PM.
6. Quotations will be opened on the same day at 4:00 PM in the principal's chamber.


23.09.25
Principal,
Mahatma Gandhi College
Lalpur, Daldali, Purulia



Name of The Work

Estimate for the renovation of Administrative building (Block-A) at M.G college at Lalpur, Dist-Purulia, West Bengal

Reference of Schedule

PWD, WB, Schedule of Rates Volume-I (Incorporation of GST Act, 2017 & all Addenda & Corrigenda of SOR, 01.12.2015), Effective From 01.11.2017

From 01.11.2017

SL NO	ITEM & PAGE NO	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE	AMOUNT
1	PAGE NO-174 ITEM NO-7	Partition with soft insulation board (of 12mm thick) as per design fitted and fixed complete (excluding the supporting framework but including necessary teak wood battens of size 40 mm & 25 mm). In Ground Floor (a) Ordinary Teak	10.66	Sq.M	516	5500.56
2	PAGE NO-172 ITEM NO-1	Wall panelling / partition with Melamine faced 3 layered flat pressed wood particle board of approved make and brand as per direction of Engineer - in - Charge of requisite grade bonded with phenol formaldehyde synthetic resin conforming to IS: 848 - 1974 (excluding the cost of supporting frame work and teak wood battens / lipping)	14.7	Sq.M	796	11701.20
3	P-195,It No-7	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor)	179.80	Sq.M	44.20	7947.16
4	PAGE NO-196 ITEM NO-10	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturer's specification) including cleaning and smoothing of surface. Two Coats	179.80	Sq.M	70.00	12586.00
Rupees: Seventy Thousand Eight Hundred Fifty Two Only			Total-			37734.92
			Add Electrification			20000.00
			Total-			57734.92
			GST @18%			10392.29
			Total-			68127.21
			CESS @ 1%			681.27
			Contingency 3%			2043.82
			GRAND TOTAL			70852.29
			Say Rs.			70852.00

[Signature]
24.07.25
Principal,
Mahatma Gandhi College
Lalpur, Dahanu, Purulia

[Signature]
Lakshmi Kanta Mahato
(DCE)
Consulting Civil Engineer
North Lake Road, Purulia
Lic No - PH/LBS-11/017P7221231197D

- * 4mm wire ISI Mark - 140 mtn.
- * 2.5 mm wire ISI " - 68 mtn.
- * AC Board - complete set - 3 Pice
- * casing 15 pice