Ph.-03252-240310 E-mail:mgclalpur@yahoo.co.in www.mahatmagandhicollegelalpur.ac.in

MAHATMA GANDHI CÖLLEGE

(NAAC Accredited Grade- "B+" w.e.f. 16.09.2016)

LALPUR • P.O.-DALDALI • DIST- PURULIA • PIN-723130 (W.B.)

Ref. No.	
----------	--

Date-....

Notice

No. MGC/Quot./23/09/NIQ-12

Dtd. 23/09/2025

Quotations are invited from eligible contractor for performing the following works within 13/10/25 (Monday). & Rs. 63,801/-

Work tender for Guard-wall at M.G. College, Lalpur

SL. NO	Subject	SPECIFICATION			
1	Guard-wall	Description of the work: See attached file			

Terms & Conditions:

- 1. GST and any other applicable taxes must be mentioned separately.
- 2. Quotation must be submitted on letterhead with seal and signature.
- 3. Work must be completed within 7 days of issuing the work order.
- 4. Vendors must submit valid trade license, PAN, and GST registration documents.
- 5. The last date of submission of the quotation is 13/10/25 (Monday) by 3:00 PM.
- 6. Quotations will be opened on the same day at 4:00 PM in the principal's chamber.

Estimate for the construction of Guard wall at M.G college at Lalpur ,Dist-Purulia, West Bengal

PWD,WB ,Schedule of Rates Volume-I (Incorporation of GST Act, 2017 & all Addenda & Corrigenda of SOR, 01 12 2015),Effective From 01 11 2017 Reference of Schedule

SL NO	ITEM & PAGE	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE	AMOUNT Rs
1	PAGE NO- 1 ITEM NO- 1	Surface Dressing of the ground in any kind of soil including removing vegetation inequalities not exceeding 15 cm depth and disposal of the rubbish within a lead upto 75 m as directed.	55.80	Sq.M	10.00	558.00
2	PAGE NO- 14 ITEM NO-1	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	55.8	Sq.M	266	14842.80
3	PAGE NO- 24 ITEM NO- 4	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement, if any, in ground floor as per relevant IS codes a) Pakur Variety	5.20	Cu.M.	4672.00	24294.40
4	PAGE NO-5 ITEM NO- 10	Pre-Constructional Anti-termite measures: (a) Anti termite treatment to bottom surface (in case of masonry foundation and basements) and the sides (upto a height of 300 mm. from bottom) of the excavation trenches with chemical emulsion by admixing chloropyrofos emulsifiable concentrates (1% concentration) with water by weight at the rate of 5Litres per sq. m. area. The work shall be carried out as per specification described in 6.2.1. of code IS- 6313 (part -II) 1981. (Mode of measurment will be the plan area of foundation treated.)				
			55.80	Sq.M	93.00	5189.40
5	PAGE NO- 189 ITEM NO- 1	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface]	55.80	Sq.M	121.00	6751.80
6	PAGE NO- 192 ITEM NO- 15	Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc. NOTE:Cement 0.152 cu.m per100 sq.m.	55.80	Sq.M	34.00	1897.20
	Rupees: Sixty five thousand six hundred ninety six only			Total- GST @18% Total-		53533.60 9636.05 63169.65
	p)				CESS @ 1% Contigency 3% AND TOTAL Say Rs.	631.70 1895.09 65696.43 65696.00

Lakshmi Kanta Mahato Consulting Civil Engineer
North Lake Road, Purulia 40No-PH/LBS-11/0917 772212519713.